

STRUCTURE PRELIMINARY GEOTECHNICAL REPORT
PLEASANT GROVE CREEK BRIDGE (WIDEN)
BRIDGE NUMBERS 19-0136L/R
Placer County, California
EA 03-1F1700; 03-PLA-65; PM R8.8

Prepared by:

BLACKBURN CONSULTING
2491 Boatman Avenue
West Sacramento, California
(916) 375-8706

November 2015

Prepared for:

Mark Thomas & Company, Inc.
7300 Folsom Blvd., Suite 203
Sacramento, CA 95826

West Sacramento Office:
2491 Boatman Ave. ▪ West Sacramento, CA 95691
(916) 375-8706 ▪ Fax (916) 375-8709



Main Auburn Office: (530) 887-1494
Fresno Office: (559) 438-8411
Modesto Office: (209) 522-6273

Geotechnical ▪ Geo-Environmental ▪ Construction Services ▪ Forensics

File No. 2602.1
November 25, 2015

Mr. Matt Brogan, PE
Mark Thomas & Company, Inc.
7300 Folsom Blvd., Suite 203
Sacramento, CA 95826

Subject: **Structure Preliminary Geotechnical Report
Pleasant Grove Creek Bridge (Widen), Bridge Numbers 19-0136L/R**
Placer County, California
EA 03-1F1700; 03-PLA-65; PM R8.8

Dear Mr. Brogan,

Blackburn Consulting (BCI) prepared this Structure Preliminary Geotechnical Report for the proposed widening of Pleasant Grove Creek Bridge (Right and Left structures) on State Route 65 in Placer County, California. BCI prepared this report in accordance with our January 16, 2014 Subcontract Agreement (SA-13143) between BCI and Mark Thomas & Company, Inc.

Thank you for the opportunity to be part of your design team. Please call us if you have questions or require additional information.

Sincerely;

BLACKBURN CONSULTING

Reviewed by:

David J. Morrell, P.E., G.E.
Senior Project Manager

Patrick Fischer, P.E., C.E.G.
Principal

Copies: 6 to Addressee

STRUCTURE PRELIMINARY GEOTECHNICAL REPORT

Pleasant Grove Creek Bridge (Widen)

Bridge Numbers 19-0136L/R

Placer County, California

EA 03-1F1700; 03-PLA-65; PM R8.8

TABLE OF CONTENTS

1	INTRODUCTION.....	1
1.1	Purpose	1
1.2	Scope of Services	1
1.3	Site Location and Description	1
2	PROJECT DESCRIPTION	2
3	EXCEPTIONS TO POLICY.....	2
4	FIELD INVESTIGATION AND TESTING PROGRAM.....	2
4.1	Subsurface Investigation and Laboratory Testing.....	2
4.2	Site Review and Geologic Mapping.....	2
5	EXISTING BRIDGE DOCUMENT REVIEW.....	2
6	SITE GEOLOGY AND SUBSURFACE CONDITIONS.....	3
6.1	General Project Area Geology	3
6.2	Subsurface Soil and Rock.....	4
6.3	Groundwater and Surface Water	4
7	PRELIMINARY GEOLOGIC HAZARDS AND SEISMIC DATA.....	4
7.1	Seismic Data and Geologic Hazards	4
7.1.1	<i>Ground Motion</i>	4
7.1.2	<i>Liquefaction</i>	5
7.1.3	<i>Fault Rupture</i>	6
7.1.4	<i>Seismic Settlement</i>	6
7.1.5	<i>Seismic Slope Instability</i>	6
8	PRELIMINARY GEOTECHNICAL RECOMMENDATIONS	6
8.1	Structure Foundations.....	6
8.2	Cuts and Fills.....	7
8.3	Erosion.....	7
8.4	Scour.....	7
9	PRELIMINARY SOIL CORROSION EVALUATION.....	7
10	CONSTRUCTION CONSIDERATIONS	8
11	SUBSURFACE EXPLORATION AND LABORATORY TESTING.....	8
12	LIMITATIONS.....	8

STRUCTURE PRELIMINARY GEOTECHNICAL REPORT

Pleasant Grove Creek Bridge (Widen)

Bridge Numbers 19-0136L/R

Placer County, California

EA 03-1F1700; 03-PLA-65; PM R8.8

TABLE OF CONTENTS (Continued)

FIGURES

Figure 1 – Vicinity Map

Figure 2 – Geologic Map

Figure 3 – Regional Fault Map

Figure 4 – Preliminary ARS Response Spectra

APPENDIX A

Preliminary Advance Planning Study Plan (Bridge No. 19-0136L/R)

As-Built Logs of Test Borings

Pleasant Grove Creek Bridge (Bridge No. 19-0136L)

Pleasant Grove Creek Bridge (Bridge No. 19-0136R)

Laboratory Test Results

From April 30, 1998 Foundation Report, Pleasant Grove Creek Bridge
at SR 65 (Bridge No. 19-136R), Prepared by Anderson Consulting Group

1 INTRODUCTION

1.1 Purpose

Mark Thomas & Company, Inc. (MTCO) retained Blackburn Consulting (BCI) to prepare this Structure Preliminary Geotechnical Report (SPGR) for the proposed widening of Pleasant Grove Creek Bridge (Right and Left structures), which is part of the overall State Route 65 (SR 65) Capacity and Operational Improvements Project located in Placer County, California. This report provides preliminary geotechnical/geologic information for advance planning purposes. Additional geotechnical studies are required for design level recommendations.

BCI prepared this SPGR for MTCO for advance planning purposes only. Do not use or rely upon this report for other locations or for final project design.

1.2 Scope of Services

To prepare this report, BCI:

- Discussed the project with the project team
- Reviewed a preliminary advance planning study plan prepared by CH2M Hill.
- Reviewed published maps and literature related to site soil, rock, and geologic conditions
- Reviewed published geotechnical data and as-built information for the existing Pleasant Grove Creek Bridge (right and left structures)
- Conducted a preliminary geologic site reconnaissance to confirm reported conditions

1.3 Site Location and Description

Pleasant Grove Creek Bridge is located on SR 65 in Placer County, California, about 0.7 miles north of the Blue Oaks Boulevard Overcrossing and 0.8 miles south of the Sunset Boulevard Overcrossing. Figure 1 presents a site vicinity map.

In the project area, SR 65 is a 4-lane divided highway with a wide unpaved median. The Pleasant Grove Creek Bridge (Left) structure was built in 1971 and consists of a 2-lane, 5-span cast-in-place reinforced concrete slab bridge supported on 16-inch Cast-In-Drilled-Hole (CIDH) piles at the abutments and bent pile extensions. The bridge is 42 feet wide and 128 feet long. The Pleasant Grove Creek Bridge (Right) structure was built in 2001 and consists of a 2-lane, 5-span cast-in-place reinforced concrete slab bridge supported on 15-inch precast, prestressed concrete piles (octagonal) at the abutments and pier pile extensions. Abutment front slopes for both bridges are covered with rock slope protection.

Within the project limits, Pleasant Grove Creek flows southwest on a shallow gradient. The creek channel contains a moderate to heavy growth of brush and marsh vegetation between and directly upstream/downstream of the existing bridges.

2 PROJECT DESCRIPTION

The right and left bridges are proposed to be widened on the outside by about 11½ to 12½ feet to accommodate new auxiliary lanes for the SR 65 Capacity and Operational Improvements Project. The widening bridges will be similar to the existing bridges, and consist of 5-span, reinforced concrete slab structures supported on piles at the abutments and pile extensions at the bents/piers.

3 EXCEPTIONS TO POLICY

No exceptions to Caltrans departmental policy are included for this SPGR.

4 FIELD INVESTIGATION AND TESTING PROGRAM

4.1 Subsurface Investigation and Laboratory Testing

New subsurface investigation and laboratory testing was not completed for this SPGR. We used subsurface data obtained for the existing structures to evaluate site conditions within the project area. See Appendix A for copies of the Logs of Test Borings (LOTB's) used in our review. Appendix A also includes copies of the laboratory test results from the April 30, 1998 Foundation Report for Pleasant Grove Creek Bridge at SR 65 (Bridge No. 19-136R), prepared by Anderson Consulting Group.

4.2 Site Review and Geologic Mapping

BCI completed a site reconnaissance to observe the site and confirm published geologic conditions. We include a discussion of area geology in Section 6.1.

5 EXISTING BRIDGE DOCUMENT REVIEW

The project team provided the following documents related to the existing bridges for our review:

- As-Built Plans, Pleasant Grove Creek Bridge (Left), Caltrans, Completed 11/09/1971, Sheets 1-5, including Log of Test Borings
- As-Built Plans, Pleasant Grove Creek Bridge (Right), Mark Thomas & Company, Inc., Completed 5/01/2001, Sheets 1-10, including Log of Test Borings
- Foundation Report (unsigned), Pleasant Grove Creek Bridge (Right), Anderson Consulting Group, 4/30/1998
- Hydrology Report, Pleasant Grove Creek Bridge at State Route 65 (Bridge No. 19-136R), Mark Thomas & Company, Inc., 12/05/1997
- Bridge Inspection Report, Pleasant Grove Creek Bridge (Bridge No. 19-136L), Caltrans, Inspection Date 10/17/2013

STRUCTURES PRELIMINARY GEOTECHNICAL REPORT

Pleasant Grove Creek Bridge (Widen)

Bridge Numbers 19-0136L/R

Placer County, California, EA 03-1F1700; 03-PLA-65; PM R8.8

BCI Job. No. 2602.1

November 25, 2015

- Bridge Inspection Report, Pleasant Grove Creek Bridge (Bridge No. 19-136R), Caltrans, Inspection Date 1/15/2014

Appendix A contains copies of the above As-Built Logs of Test Borings (LOTB's) sheets as well as the laboratory test results from the Foundation Report.

6 SITE GEOLOGY AND SUBSURFACE CONDITIONS

6.1 General Project Area Geology

The project area lies on the eastern margin of the Great Valley Geomorphic Province (Sacramento Valley portion). The Great Valley is bordered by the Cascade and Klamath Ranges to the north, the Coast Ranges to the west, and the Sierra Nevada to the east. The valley was formed by tilting of the Sierran Block with the western side dropping to form the valley and the eastern side uplifted to form the Sierra Nevada. The western slope of the Sierra Nevada is underlain by intrusive, volcanic, and metamorphic rock. Valley deposits are characterized by a thick sequence of alluvial, lacustrine, and marine sediments. The thickness of the sediments varies from a thin veneer at the valley margin, to thousands of feet in the central portion. In the project area, granitic rock and volcanic deposits occur along the valley margin.

Based on review of published geologic mapping¹, our site review, and available subsurface information, the project area is underlain by the Quaternary age Turlock Lake Formation. The Turlock Lake Formation is typically composed of semi-consolidated, alluvial deposits that consist of stiff to hard clays and silts and medium dense to dense sands and gravels. These sediments are alluvial deposits derived from granitic rock of the Sierra Nevada and deposited over 450,000 years ago.

The As-Built Log of Test Borings for the Pleasant Grove Creek Bridge (Right) indicate that Mehrten Formation conglomerate is present beneath the Turlock Lake Formation at a depth of about 35 feet below the creek channel bottom. The conglomerate consists primarily of cobbles in a well-cemented matrix of andesitic sand and silt, and often contains interbedded layers of sandstone, siltstone, and lenses of mudflow breccia. Bedding of sediments and flows within the Mehrten Formation typically dip gently (2 to 4 degrees) to the west/southwest. These volcanic materials were deposited during Miocene time (5 to 20 million years ago).

Figure 2 presents a regional geologic map showing the site location and geologic units.

¹ Mulder, J., 2007, Geologic Map of the Late Cenozoic Deposits of the Sacramento Valley, California Department of Water Resources, modified digital reproduction of the Geologic Map of the Late Cenozoic Deposits of the Sacramento Valley and Northern Sierran Foothills, California, by Edward J. Helley and David S. Harwood (USGS Publication MF-1790, 1985).

6.2 Subsurface Soil and Rock

We describe the anticipated subsurface soil and rock conditions at the site based on our site reconnaissance, review of the As-Built Log of Test Borings for the existing structures and review of the April 30, 1998 Foundation Report for the right structure.

Existing bridge approach fills extend up to a maximum height of about 7 feet above surrounding grades at the abutment locations. Several feet of recent alluvium (soft sandy clay and loose sand) exist within the channel bed. Beneath the approach fill and alluvium, the borings generally encountered interlayered, hard silts and clays, and dense to very dense (occasionally medium dense) silty sand, clayey sand and poorly graded sand extending to a depth of about 35 feet (Elev. 69.5 ft, NGVD 29 datum) below the existing channel bottom. These soils were variably cemented and are underlain by Mehrten Formation conglomerate (strongly cemented, soft rock) to the maximum depths explored.

Appendix A contains copies of the As-Built Logs of Test Borings (LOTB's) sheets.

6.3 Groundwater and Surface Water

The As-Built Log of Test Borings for the right structure indicate that groundwater was encountered at a depth of about 17 feet (Elev. 87.0-88.0 ft) below the existing channel bottom in November, 1997. We reviewed groundwater level data made available by the California Department of Water Resources (Historical Data Map Interface website). The closest well data (about 1,700 feet northeast of the project) indicates that the regional groundwater table fluctuated between approximate elevations 53.0-60.0 ft. between 1997 to 2008 (last measurement). The higher groundwater levels observed in the borings for the right structure likely resulted from infiltration of the creek surface water into the underlying soil units.

Based our review of historical satellite imagery (Google Earth™), it appears that surface water is present within the creek channel throughout the year, with higher flows occurring during the rainy season. There was 1-2 feet of relatively stagnant water beneath the bridges during our November 16, 2015 site visit.

7 PRELIMINARY GEOLOGIC HAZARDS AND SEISMIC DATA

7.1 Seismic Data and Geologic Hazards

7.1.1 Ground Motion

BCI used Caltrans ARS Online (Version 2.3.06) to develop a preliminary Acceleration Response Spectrum (ARS) Spectra Curve for preliminary design of the new bridge structures.

We summarize the data in Table 1. Figure 4 shows a graphical display of the preliminary ARS Response Spectra Curve.

STRUCTURES PRELIMINARY GEOTECHNICAL REPORT

Pleasant Grove Creek Bridge (Widen)

Bridge Numbers 19-0136L/R

Placer County, California, EA 03-1F1700; 03-PLA-65; PM R8.8

BCI Job. No. 2602.1

November 25, 2015

TABLE 1 – PRELIMINARY GROUND MOTION STUDY RESULTS	
Peak Ground Acceleration (PGA)	0.23g
V_{S30} (Small Strain Shear Wave Velocity) ¹	1,200 feet per second (365 m/s)
Near Fault Factor	Yes
Basin Amplification Factor	NA
Controlling Deterministic Scenario	Minimum Deterministic: <ul style="list-style-type: none"> ➤ Style: Vertical strike-slip ➤ Maximum Magnitude (M_{max}): 6.5 ➤ Site to fault distance (R_{RUP}): 7.5 mi
Nearest Late Quaternary Fault	Foothills Fault System – Deadman Fault <ul style="list-style-type: none"> ➤ Fault ID Number: 422 ➤ Style: Normal ➤ Dip: 50 degrees, West ➤ Maximum Magnitude (M_{max}): 6.2 ➤ Site-to-Fault Distance (R_{RUP})²: 9.8 miles/15.8 km
RECOMMENDED PRELIMINARY DESIGN RESPONSE SPECTRUM	Envelope that consists of the minimum deterministic spectrum and the probabilistic spectrum (probability of exceedance equal to 5% in 50 years, a 975-year return period). <ul style="list-style-type: none"> ➤ ARS Response Spectra - See Figure 4 ➤ PGA = 0.23g (based on minimum deterministic spectrum) ➤ M_{max} = 6.5

1) Preliminary V_{S30} value based on the lower limit of shear wave velocity for Soil Profile Type C (very dense soil and soft rock)

2) R_{RUP} is defined as the closest distance to the fault rupture plane (as defined in Caltrans’ “Methodology for Developing Design Response Spectrum for Use in Seismic Design Recommendations,” Appendix B, November 2012)

The information provided in Table 1 and the Preliminary Design Response Spectra will need to be updated for final design.

7.1.2 Liquefaction

Liquefaction can occur when saturated, loose to medium dense, granular soils (generally within 50 feet of the surface), or specifically defined cohesive soils, are subjected to ground shaking. According to our document and site review, non-liquefiable soils (medium dense to very dense granular soils, very stiff to hard, cohesive soils, and/or soft rock) are present at relatively shallow depths at planned structure locations. We consider the potential for detrimental liquefaction to be low at planned structure locations throughout the project.

7.1.3 *Fault Rupture*

Faulting is not mapped through the site, and the site does not lie within or adjacent to a Fault Rupture Hazard Zone (Bryant and Hart, 2007). Based on the Caltrans ARS Online (V2.3.06), the closest seismic source is a portion of the Foothills Fault System (Deadman Fault) located approximately 9.8 miles (15.8 km) to the east. We consider the potential for fault rupture within the project area to be very low. Figure 3 shows the general fault locations in the region.

7.1.4 *Seismic Settlement*

During a seismic event, ground shaking can cause densification of granular soil above the water table that can result in settlement of the ground surface. Based on our review, medium dense to very dense/hard soils and/or rock is present at relatively shallow depths throughout the project area and probable ground motions are relatively low (Peak Ground Acceleration of 0.23g). We consider the potential for detrimental seismic settlement within the project area to be low for native soil/rock and engineered fill, provided engineered fills are constructed in accordance with Caltrans guidelines.

7.1.5 *Seismic Slope Instability*

Based on the geologic conditions and past performance, we consider the potential for seismic slope instability in the form of landslides and mudslides within the project area to be very low. Similarly, we consider the potential for seismic instability of engineered cut or fill slopes constructed at typical allowable gradients of 2H:1V or flatter to be low.

8 PRELIMINARY GEOTECHNICAL RECOMMENDATIONS

8.1 Structure Foundations

The Pleasant Grove Creek Bridge (Left) structure was built in 1971 and is supported on 16-inch Cast-In-Drilled-Hole (CIDH) piles at the abutments and bent pile extensions. The piles were Class 45 (45 ton) with a specified tip elevation of 85.0 ft.

The Pleasant Grove Creek Bridge (Right) structure was built in 2001 and is supported on driven 15-inch precast, prestressed concrete piles (octagonal) at the abutments and pier pile extensions. The abutment piles were Class 45 and had average pile tip elevations of 90-91 feet based on the as-built plans. The pier pile extensions were Class 70 and had average pile tip elevations of about 79 feet. Although not indicated on the as-built plans, it is likely that undersize drilling to assist driving was necessary since it was recommended in the foundation report.

The subsurface conditions encountered in the existing borings indicate that the site is conducive for either driven or cast-in-drilled-hole (CIDH) piles. Since CIDH piles would likely require installation using the “wet” method (temporary casing, slurry drilling, gamma gamma inspection and minimum 24-inch diameter piles) due to high groundwater and surface water intrusion, we favor the use of driven piles over CIDH piles. Driven concrete or closed-end steel pipe piles

STRUCTURES PRELIMINARY GEOTECHNICAL REPORT

Pleasant Grove Creek Bridge (Widen)

Bridge Numbers 19-0136L/R

Placer County, California, EA 03-1F1700; 03-PLA-65; PM R8.8

BCI Job. No. 2602.1

November 25, 2015

would likely require undersize drilling to assist driving through very dense/hard soil conditions in order to reach specified tip elevations. Open-ended pipe piles and/or steel HP piles could likely be driven to specified tip elevations without drilling to assist pile driving, although heavier sections than Class 90 piles may be necessary to avoid damage to the piles during driving (i.e. Class 140 PP14x0.438 pipe piles or HP10x57 piles). We anticipate that specified tip elevations for Class 90/140 piles will range from about 75.0 feet to 85.0 feet.

8.2 Cuts and Fills

Most cuts and cut slopes are expected to occur within engineered fill placed for existing improvements, and within alluvial sediments that consist of medium dense to very dense, silty to clayey sands and hard silts and clays. We expect that cut slopes will be stable at slopes of 2H:1V or flatter within native soils and engineered fills.

We did not identify areas of potentially soft/compressible soils within the existing subsurface information or during our site reconnaissance for those areas that are likely to have significant, engineered fills constructed. We anticipate that settlement of engineered fill established on appropriately prepared subgrade will be minimal and occur primarily during fill placement. Settlement waiting periods are not expected. We expect engineered fill slopes constructed of local materials will be stable at gradients of 2H:1V or flatter. A slope gradient of 1.5H:1V can be used in front of abutments. Rock slope protection should be used to protect abutment slopes from scour and erosion.

8.3 Erosion

Embankment slopes and areas disrupted by grading are susceptible to erosion from surface runoff. Cut and fill slopes will require erosion control, such as vegetation, and control of surface runoff.

8.4 Scour

We did not observe evidence of significant scour at the abutments during our November 16, 2015 site visit, but we could not examine the bents/piers for scour since the cloudy water limited visibility.

Bridge inspection reports referenced in Section 5 did not disclose any scour issues at the bridges. The previous Hydrology Report for the right structure indicated an expected pier scour of 3.7 feet.

9 PRELIMINARY SOIL CORROSION EVALUATION

The April 30, 1998 Foundation Report for the right structure included two sulfate/chloride corrosion tests conducted on soil samples obtained from Boring B97-8, with all results less than 50 ppm. Based on available subsurface/corrosion test data, and our local experience, the soil and

STRUCTURES PRELIMINARY GEOTECHNICAL REPORT

Pleasant Grove Creek Bridge (Widen)

Bridge Numbers 19-0136L/R

Placer County, California, EA 03-1F1700; 03-PLA-65; PM R8.8

BCI Job. No. 2602.1

November 25, 2015

rock within the project area is generally expected to be non-corrosive to structural elements (as defined by Caltrans, 2012, Corrosion Guidelines, Version 2.0).

10 CONSTRUCTION CONSIDERATIONS

Excavation and Dewatering: Excavations within soil can be achieved using typical heavy-duty construction equipment. Excavations that extend below the creek bed or surface water level will require dewatering using sump pumps and/or diking/diversion of the creek. To reduce dewatering construction impacts and associated costs, we strongly recommend scheduling foundation construction during the dry season (July through October).

Pile Installation: Refer to Section 8.1 for a discussion of construction considerations related to pile installation at the site.

11 SUBSURFACE EXPLORATION AND LABORATORY TESTING

Additional subsurface exploration and laboratory testing will be required to provide the design level foundation report for widening the bridges. Specifically, we recommend the following:

- Drill, log and sample a minimum of one boring at each proposed bridge abutment for to depths of 50 to 60 feet
- Record groundwater depths during drilling
- Complete laboratory tests that include moisture content, density, unconfined compressive strength, direct shear, maximum density (proctor), R-value, and soil corrosivity

12 LIMITATIONS

This SPGR is based on site review and existing structure document review noted in Section 5, and is not intended for final design. Additional study, including subsurface exploration, laboratory testing, and analyses are required for final design. BCI performed these services in accordance with generally accepted geotechnical engineering principles and practices currently used in this area. We do not warranty our services.

**STRUCTURE PRELIMINARY GEOTECHNICAL REPORT
PLEASANT GROVE CREEK BRIDGE (WIDEN)
BRIDGE NUMBERS 19-0136L/R
Placer County, California
EA 03-1F1700; 03-PLA-65; PM R8.8**

FIGURES


Figure 1 – Vicinity Map

Figure 2 – Geologic Map

Figure 3 – Regional Fault Map

Figure 4 – Preliminary ARS Response Spectra





SOURCE: USGS Roseville and Rocklin Quadrangles, 7.5 Minute Series topographic, 1:24000, dated 2012.



SCALE: 1"=4,000'




2491 Boatman Avenue
 West Sacramento, CA 95691
 Phone: (916) 375-8706
 Fax: (916) 375-8709
 www.blackburnconsulting.com

VICINITY MAP
 Pleasant Grove Creek Bridge (Widen)
 Bridge No's 19-0136 L/R
 Placer County, California





File No. 2602.1

November 2015

Figure 1



LEGEND

-  Quaternary Alluvium
-  Riverbank Formation (upper member)
-  Turlock Lake Formation
-  Mehrten Formation



SCALE: 1"=4,000'

SOURCE: Mulder, J., 2007, Geologic Map of the Late Cenozoic Deposits of the Sacramento Valley, California Department of Water Resources, modified digital reproduction of the Geologic Map of the Late Cenozoic Deposits of the Sacramento Valley and Northern Sierran Foothills, California, by Edward J. Helley and David S. Harwood (USGS Publication MF-1790, 1985).

11/24/2015 2602.1 Fig2.Pleasant Grove Creek (Widen).dwg




2491 Boatman Avenue
West Sacramento, CA 95691
Phone: (916) 375-8706
Fax: (916) 375-8709
www.blackburnconsulting.com

GEOLOGIC MAP
Pleasant Grove Creek Bridge (Widen)
Bridge No's 19-0136 L/R
Placer County, California

File No. 2602.1

November 2015

Figure 2



SOURCE: Caltrans ARS Online (V2.3.06)



Not to Scale

1/12/2015 2602.1 Figs:Pleasant Grove Creek (Widen).dwg



2491 Boatman Avenue
 West Sacramento, CA 95691
 Phone: (916) 375-8706
 Fax: (916) 375-8709
 www.blackburnconsulting.com


REGIONAL FAULT MAP
 Pleasant Grove Creek Bridge (Widen)
 Bridge No's 19-0136 L/R
 Placer County, California

File No. 2602.1

November 2015

Figure 3

Preliminary ARS Curve (5% Damping) - ARS Online (V2.3.06)
Pleasant Grove Creek Bridge at State Route 65



1/12/2015 2602.1 Fig4-Pleasant Grove Creek (Widen).dwg



2491 Boatman Avenue
 West Sacramento, CA 95691
 Phone: (916) 375-8706
 Fax: (916) 375-8709
 www.blackburnconsulting.com

PRELIMINARY ARS RESPONSE SPECTRUM
 Pleasant Grove Creek Bridge (Widen)
 Bridge No's 19-0136 L/R
 Placer County, California

File No. 2602.1
November 2015
Figure 4

**STRUCTURE PRELIMINARY GEOTECHNICAL REPORT
PLEASANT GROVE CREEK BRIDGE (WIDEN)
BRIDGE NUMBERS 19-0136L/R
Placer County, California
EA 03-1F1700; 03-PLA-65; PM R8.8**

APPENDIX A

Preliminary Advance Planning Study Plan (Bridge No. 19-0136L/R)


As Built Logs of Test Borings (Bridge No. 19-0136L/R)

Laboratory Test Results




DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT
03	Plā	65	
PCTPA 299 NEVADA ST. AUBURN, CA 95603 CH2M HILL 2485 NATOMAS PARK DR. STE 600 SACRAMENTO, CA 95833			

- Vehicular Traffic
1. — New alignment. No traffic at the site.
 2. — Traffic will be detoured away from the site.
 3. X Traffic will be carried on the structure. Stage construction will not be required.
 4. — Traffic will pass under the structure on




ELEVATION
 1" = 20'
 (SHOWN FOR Br. No. 19-0136R, Br. No. 19-0136L SIMILAR)




PLAN
 1" = 20'

- LEGEND**
- Indicates Existing Structure
 - Indicates New Construction
 - /// Indicates Bridge Removal (Portion)
 - ▽ Indicates Ordinary High Water



TYPICAL SECTION
 Br No 19-0136R
 1" = 5'



TYPICAL SECTION
 Br No 19-0136L
 1" = 5'

DATE OF ESTIMATE	10-16-15
BRIDGE REMOVAL	= \$6,700
STRUCTURE DEPTH	= 1'-3 1/2" (L+), 1'-4" (R+)
LENGTH	= 128.19'± (L+), 140'± (R+)
WIDTH	= 12'-5" (L+), 11'-8" (R+)
AREA	= 3,225 SQFT
COST/ØFT INCLUDING 10% MOBILIZATION & 25% CONTINGENCY	= \$200
TOTAL COST	= \$651,700

* Match existing grade and cross slope.

X	DESIGN OVERSIGHT
X	SIGN OFF DATE

NOTE:
 THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.




DESIGNED BY	JENNIFER ELWOOD	DATE	10/16/15
DRAWN BY	ED MAEHLER	DATE	10/16/15
CHECKED BY	MARK BRADY	DATE	10/16/15
APPROVED	X	DATE	X

PLANNING STUDY	
PLEASANT GROVE CREEK BRIDGE (WIDEN)	
BRIDGE NO. 19-0136L/R	UNIT: 03
SCALE: AS SHOWN	PROJECT NUMBER & PHASE: X



FIELD STUDY
DRAWN BY
CHECKED BY
APPROVED BY

BRIDGE DEPARTMENT
ENGINEERING GEOLOGY SECTION

48



NOTE: Classification of earth material as shown on this sheet is based upon field inspection and is not to be construed to imply mechanical analysis.



NO GROUND WATER ENCOUNTERED DURING THIS INVESTIGATION BY BRIDGE DEPT. GEOLOGY SECTION DATE July 1968

DIST.	COUNTY	ROUTE	POST MILES-TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
03	PL	65, 256	5.4/13.5, 5.7/60	48	55

A. P. Duggan
DESIGN SECTION SUPERVISOR
REGISTERED CIVIL ENGINEER NO. 11144
DATE APPROVED May 11, 1970


AS BUILT PLANS
Contract No. 03-078934
Date Completed 11-9-71
Document No. 3000 2012

STATE OF CALIFORNIA TRANSPORTATION AGENCY DEPARTMENT OF PUBLIC WORKS DIVISION OF HIGHWAYS					
PLEASANT GROVE CREEK					
LOG OF TEST BORINGS					
BRIDGE NO.	POST MILE	DRAWING NO.	SHEET	OF	
19-136	8.0		5	5	
REVISION DATES (PRELIMINARY STAGE ONLY)					
1/2/80					

I HEREBY CERTIFY THAT THIS IS A TRUE AND ACCURATE COPY OF THE ABOVE DOCUMENT TAKEN UNDER MY DIRECTION AND CONTROL ON THIS DATE IN SACRAMENTO, CALIFORNIA PURSUANT TO AUTHORIZATION BY THE DIRECTOR OF PUBLIC WORKS.
DATE 4/11/72 SIGNATURE [Signature] TITLE SR. FMO

DIST.	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
3	PLA	65	R8.3 / T13.0	208	216

Tom Blackburn 4-28-98
 GEOTECHNICAL PROFESSIONAL
 2-22-99
 PLANS APPROVAL DATE
 CITY OF LINCOLN
 1390 FIRST STREET
 LINCOLN, CA 95646



ANDERSON CONSULTING GROUP
 631 COMMERCE DRIVE
 ROSEVILLE, CA 95678


The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

BENCHMARK


Horizontal coordinates and stations are CCS83, Zone 2, in U.S. survey feet based on NAD 83 (Epoch 1991.35) datum. Vertical elevations are in feet on the NGVD 29 datum. (To convert elevations to the NAVD 88 datum, add 0.710m).
 CalTrans 19-131 "A3" Station 455+57.60 Lt 82.43'
 T-Bar N 2,056,989.311'
 E 6,760,987.903'
 Elev. 117.865'
 CalTrans 19-130 "A3" Station 434+49.37 Lt 82.50'
 T-Bar N 2,054,881.189'
 E 6,760,985.772'
 Elev. 114.37'

AS BUILT



CORRECTIONS BY GARY DELFERY
 CONTRACT NO. 03-447504
 DATE 05-01-01
 NO ASBUILT CHANGES




PLAN VIEW
 SCALE: 1" = 20'



PROFILE VIEW
 HORIZONTAL SCALE: 1" = 10'
 VERTICAL SCALE: 1" = 5'



LEGEND OF BORING OPERATIONS
 BORE LOGGING
 HAND BORING
 AUGER BORING (DRY)
 NOTES:
 3.0" DIAMETER SAMPLER CONSISTED OF A SPLIT-SPoon SAMPLER EQUIPPED WITH 2.5" O.D. AND 2.375" I.D. BRASS LINERS.
 2.0" DIAMETER SAMPLER CONSISTED OF A STANDARD PENETRATION TEST SAMPLER WITHOUT LINERS; EXCEPT B97-9 WHICH WAS A HAND SAMPLER.
 SAMPLERS WERE DRIVEN INTO THE GROUND AUTOMATIC TRIP HAMMER FALLING 30", EXCEPT FOR THE HAND SAMPLER.



CONSISTENCY CLASSIFICATION FOR SOILS	
According to the Standard Penetration Test	
Cohesive	Very soft Soft Stiff Very stiff Hard Very hard
Granular	Very loose Loose Medium dense Dense Very dense
Penetration Index (Blows / Ft)	0-4 5-19 20-29 30-59 60-79 >80

NOTE: Classification of earth material as shown on this sheet is based upon field inspection and is not to be construed to imply mechanical analysis.

DESIGN OVERSIGHT
 SIGN OFF DATE 6-10-98

DRAWN BY LOREE HAMMER
 CHECKED BY ROBERT B. LOKTEFF

ROBERT B. LOKTEFF
 FIELD INVESTIGATOR
 DATE JANUARY 1998

PREPARED FOR THE
 STATE OF CALIFORNIA
 DEPARTMENT OF TRANSPORTATION




ROBERT B. LOKTEFF
 PROJECT ENGINEER
 BRIDGE NO. 19-136R
 POST MILE R 8.7

PLEASANT GROVE CREEK BRIDGE
 LOG OF TEST BORINGS

ORIGINAL SCALE IN INCHES FOR REDUCED PLANS 0 1 2 3

CU 03198
 EA 447501

REVISION DATES (PRELIMINARY STAGE ONLY)	SHEET	OF
4/28/98	10	10



SAMPLE NO.		1	2	3
INITIAL	WATER CONTENT, %	9.7	10.9	9.6
	DRY DENSITY, pcf	110.5	110.0	108.5
	SATURATION, %	51.9	57.5	48.5
	VOID RATIO	0.497	0.504	0.524
	DIAMETER, in	2.38	2.38	2.38
	HEIGHT, in	1.00	1.00	1.00
AT TEST	WATER CONTENT, %	17.9	17.6	17.9
	DRY DENSITY, pcf	109.6	111.3	110.6
	SATURATION, %	93.1	95.8	95.7
	VOID RATIO	0.509	0.486	0.496
	DIAMETER, in	2.38	2.38	2.38
	HEIGHT, in	1.01	0.99	0.98
NORMAL STRESS, psf		250	500	1000
MAXIMUM SHEAR, psf		644	845	1251
RESIDUAL SHEAR, psf				
Strain rate, %/min		0.194	0.193	0.164

SAMPLE DATA

SAMPLE TYPE: In situ
 DESCRIPTION: Very dark grayish brown sandy lean clay (CL)
 LL= 30 PL= 17 PI= 13.0
 SPECIFIC GRAVITY= 2.65
 REMARKS:

CLIENT:

PROJECT: Route 65 Materials Report




SAMPLE LOCATION: B97-8; L1

PROJ. NO.: 4143.3

DATE: 12-3-97

DIRECT SHEAR TEST REPORT

ANDERSON CONSULTING GROUP



SAMPLE NO.		1	2	3
INITIAL	WATER CONTENT, %	16.8	15.8	16.7
	DRY DENSITY, pcf	112.2	110.4	111.5
	SATURATION, %	93.8	84.1	91.3
	VOID RATIO	0.474	0.498	0.483
	DIAMETER, in	2.38	2.38	2.38
	HEIGHT, in	1.00	1.00	1.00
AT TEST	WATER CONTENT, %	18.8	19.2	19.6
	DRY DENSITY, pcf	112.9	110.2	110.3
	SATURATION, %	106.9	101.3	103.9
	VOID RATIO	0.465	0.501	0.500
	DIAMETER, in	2.38	2.38	2.38
	HEIGHT, in	0.99	1.00	1.01
NORMAL STRESS, psf		1000	500	250
MAXIMUM SHEAR, psf		1869	891	884
RESIDUAL SHEAR, psf				
Strain rate, %/min		0.191	0.177	0.191

SAMPLE DATA

SAMPLE TYPE: In situ
 DESCRIPTION: Dark brown clayey sand (SC)
 LL= 37 PL= 19 PI= 18.0
 SPECIFIC GRAVITY= 2.65
 REMARKS:

CLIENT:

PROJECT: Route 65 / Pleasant Grove Creek Bridge




SAMPLE LOCATION: B97-10; L2

PROJ. NO.: 4143.3

DATE: 12-10-97

DIRECT SHEAR TEST REPORT

ANDERSON CONSULTING GROUP



SAMPLE NO.		1	2	3
INITIAL	WATER CONTENT, %	17.7	19.4	19.5
	DRY DENSITY, pcf	104.9	104.9	103.0
	SATURATION, %	81.3	89.2	85.4
	VOID RATIO	0.577	0.577	0.606
	DIAMETER, in	2.38	2.38	2.38
	HEIGHT, in	1.00	1.00	1.00
AT TEST	WATER CONTENT, %	21.2	21.5	22.1
	DRY DENSITY, pcf	105.9	106.1	105.1
	SATURATION, %	100.0	101.6	102.2
	VOID RATIO	0.563	0.560	0.574
	DIAMETER, in	2.38	2.38	2.38
	HEIGHT, in	0.99	0.99	0.98
NORMAL STRESS, psf		500	1000	2000
MAXIMUM SHEAR, psf		1365	1986	3715
RESIDUAL SHEAR, psf				
Strain rate, %/min		0.160	0.170	0.156




SAMPLE DATA
 SAMPLE TYPE: In situ
 DESCRIPTION: Yellowish red
 clayey sand with gravel (SC)
 LL= PL= PI=
 SPECIFIC GRAVITY= 2.65
 REMARKS:

CLIENT:
 PROJECT: Route 65 / Pleasant Grove Creek
 Bridge
 SAMPLE LOCATION: B97-10; L3

PROJ. NO.: 4143.3 DATE: 12-12-97

DIRECT SHEAR TEST REPORT

ANDERSON CONSULTING GROUP



SAMPLE NO.		1	2	3
INITIAL	WATER CONTENT, %	29.7	26.0	26.3
	DRY DENSITY, pcf	85.8	93.3	94.5
	SATURATION, %	84.7	89.1	92.9
	VOID RATIO	0.928	0.773	0.751
	DIAMETER, in	2.38	2.38	2.38
	HEIGHT, in	1.00	1.00	1.00
AT TEST	WATER CONTENT, %	34.5	30.2	28.4
	DRY DENSITY, pcf	86.6	94.4	96.5
	SATURATION, %	100.3	106.6	105.3
	VOID RATIO	0.911	0.752	0.714
	DIAMETER, in	2.38	2.38	2.38
	HEIGHT, in	0.99	0.99	0.98
NORMAL STRESS, psf		1000	2000	3000
MAXIMUM SHEAR, psf		1680	5493	6689
RESIDUAL SHEAR, psf				
Strain rate, %/min		0.160	0.144	0.137




SAMPLE DATA
 SAMPLE TYPE: In situ
 DESCRIPTION: Brown silt with sand
 LL= 46 PL= 30 PI= 16.0
 SPECIFIC GRAVITY= 2.65
 REMARKS:

CLIENT:
 PROJECT: Route 65 / Pleasant Grove Creek Bridge
 SAMPLE LOCATION: B97-8; L4

PROJ. NO.: 4143.3 DATE: 12-5-97

DIRECT SHEAR TEST REPORT

ANDERSON CONSULTING GROUP



SAMPLE NO.		1	2	3
INITIAL	WATER CONTENT, %	42.6	42.1	42.1
	DRY DENSITY, pcf	78.1	78.9	78.4
	SATURATION, %	101.0	101.6	100.6
	VOID RATIO	1.119	1.098	1.109
	DIAMETER, in	2.38	2.38	2.38
	HEIGHT, in	1.00	1.00	1.00
AT TEST	WATER CONTENT, %	42.5	41.3	41.6
	DRY DENSITY, pcf	79.2	80.7	81.2
	SATURATION, %	103.5	104.2	106.1
	VOID RATIO	1.089	1.051	1.038
	DIAMETER, in	2.38	2.38	2.38
	HEIGHT, in	0.99	0.98	0.97
NORMAL STRESS, psf		2000	3000	4000
MAXIMUM SHEAR, psf		2405	3582	4284
RESIDUAL SHEAR, psf				
Strain rate, %/min		0.164	0.151	0.144




SAMPLE DATA
 SAMPLE TYPE: In situ
 DESCRIPTION: Light brownish silt with sand (ML)
 LL= 44 PL= 39 PI= 5.0
 SPECIFIC GRAVITY= 2.65
 REMARKS:

CLIENT:
 PROJECT: Route 65 / Pleasant Grove Creek Bridge
 SAMPLE LOCATION: B97-10; L5

PROJ. NO.: 4143.3 DATE: 12-12-97

DIRECT SHEAR TEST REPORT

ANDERSON CONSULTING GROUP



SAMPLE NO.		1	2	3
INITIAL	WATER CONTENT, %	27.3	30.5	33.0
	DRY DENSITY, pcf	92.4	91.7	88.6
	SATURATION, %	91.8	100.4	100.8
	VOID RATIO	0.790	0.805	0.868
	DIAMETER, in	2.38	2.38	2.38
	HEIGHT, in	1.00	1.00	1.00
AT TEST	WATER CONTENT, %	30.3	29.2	29.8
	DRY DENSITY, pcf	94.6	94.6	92.1
	SATURATION, %	107.4	103.3	99.1
	VOID RATIO	0.748	0.749	0.797
	DIAMETER, in	2.38	2.38	2.38
	HEIGHT, in	0.98	0.97	0.96
NORMAL STRESS, psf		2000	3000	4000
MAXIMUM SHEAR, psf		3686	4005	5048
RESIDUAL SHEAR, psf				
Strain rate, %/min		0.161	0.161	0.164

SAMPLE DATA
 SAMPLE TYPE: In situ
 DESCRIPTION: Dark yellowish brown silty sand with gravel
 LL= PL= PI=
 SPECIFIC GRAVITY= 2.65
 REMARKS:


CLIENT:
 PROJECT: Route / 65 Pleasant Grove Creek Bridge
 SAMPLE LOCATION: B97-10; L6

PROJ. NO.: 4143.3 DATE: 12-22-97

DIRECT SHEAR TEST REPORT

ANDERSON CONSULTING GROUP

LIQUID AND PLASTIC LIMITS TEST REPORT



Location + Description	LL	PL	PI	-200	ASTM D 2487-85
● B97-8; L1; Very dark grayish brown sandy lean clay	30	17	13	53.7	CL, Sandy lean clay


Project No.: 4143.3
 Project: Route 65 / Pleasant Grove Creek Bridge

Client:
 Location: B97-8; L1

Date: 12-9-97

Remarks:

LIQUID AND PLASTIC LIMITS TEST REPORT




Location + Description	LL	PL	PI	-200	ASTM D 2487-85
● B97-8; B-2; Brown lean clay with sand	43	25	18	72.3	CL, Lean clay with sand

Project No.: 4143.3
 Project: Route 65 / Pleasant Grove Creek Bridge
 Client:
 Location: B97-8; B-2
 Date: 12-29-97

Remarks:

LIQUID AND PLASTIC LIMITS TEST REPORT



Location + Description	LL	PL	PI	-200	ASTM D 2487-85
● B97-8; L4; Brown silt with sand	46	30	16	81.1	ML, Silt with sand


Project No.: 4143.2
 Project: Route 65 / Pleasant Grove Creek Bridge

Client:
 Location: B97-8; L4

Date: 12-9-97

Remarks:

LIQUID AND PLASTIC LIMITS TEST REPORT



Location + Description	LL	PL	PI	-200	ASTM D 2487-85
● B97-8; B-4 Strong brown lean clay	44	25	19	93.1	CL, Lean clay


Project No.: 4143.3
 Project: Route 65 / Pleasant Grove Creek Bridge

Client:
 Location: B-97-8; B-4

Date: 1-2-98

Remarks:

LIQUID AND PLASTIC LIMITS TEST REPORT




Location + Description	LL	PL	PI	-200	ASTM D 2487-85
● B97-10; L2; Dark brown clayey sand (SC)	37	19	18	39.4	SC, Clayey sand

Project No.: 4143.3
 Project: Route 65 / Pleasant Grove Creek Bridge
 Client:
 Location: B97-10; L2
 Date: 12-15-97

Remarks:

LIQUID AND PLASTIC LIMITS TEST REPORT




Location + Description	LL	PL	PI	-200	ASTM D 2487-85
● B97-10; B-3; Grayish brown lean clay with sand	42	25	17	75.6	CL, Lean clay with sand

Project No.: 4143.3
 Project: Route 65 / Pleasant Grove Creek Bridge
 Client:
 Location: B97-10; B-3
 Date: 12-29-97

Remarks:

LIQUID AND PLASTIC LIMITS TEST REPORT



Location + Description	LL	PL	PI	-200	ASTM D 2487-85
● B97-10; B-4 Yellowish brown silt	44	28	16	91.5	ML, Silt


Project No.: 4143.3
 Project: Route 65 / Pleasant Grove Creek Bridge

Client:
 Location: B97-10; B-4

Date: 1-2-98

Remarks:

LIQUID AND PLASTIC LIMITS TEST REPORT




Location + Description	LL	PL	PI	-200	ASTM D 2487-85
● B97-10; L5; Light brownish gray silt with sand	44	39	5	79.8	ML, Silt with sand

Project No.: 4143.3
 Project: Route 65 / Pleasant Grove Creek Bridge
 Client:
 Location: B97-10; L5
 Date: 12-15-97

Remarks:

LIQUID AND PLASTIC LIMITS TEST REPORT



Location + Description	LL	PL	PI	-200	ASTM D 2487-85
● B97-10; L6 Dark yellowish brown sand with silt & gravel	NV	NP	None	11.1	SP-SM, Poorly graded sand with silt and gravel

NV - Non-Viscous NP - Non-Plastic


Project No.: 4143.3
 Project: Route 65 / Pleasant Grove Creek Bridge

 Client:
 Location: B97-10; L6

 Date: 1-2-98

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT



Test	%+75mm	% GRAVEL	% SAND	% SILT	% CLAY
● 7	0.0	9.2	70.1	20.7	


LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
●		1.95	0.41	0.29	0.139				

MATERIAL DESCRIPTION	USCS	AASHTO
● Brown silty sand	SM	

Project No.: 4143.3
 Project: Route 65 / Pleasant Grove Creek Bridge
 ● Location: B97-8; B-5
 Date: 1-2-98

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT



Test	%+75mm	% GRAVEL	% SAND	% SILT	% CLAY
● 8	0.0	15.6	58.2	26.2	

LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
●		5.07	0.73	0.43	0.110				


MATERIAL DESCRIPTION	USCS	AASHTO
● Brown silty sand with gravel	SM	

Project No.: 4143.3
 Project: Route 65 / Pleasant Grove Creek Bridge
 ● Location: B97-8; B-7 & B-8 combined

Date: 1-2-98

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT




Test	% +75 mm	% GRAVEL	% SAND	% SILT	% CLAY
● 4	0.0	31.0	61.6	7.4	

LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
●		15.67	2.09	1.22	0.537	0.2483	0.1445	0.95	14.5

MATERIAL DESCRIPTION	USCS	AASHTO
● Drk yellowish brown sand with clay and gravel	SP-SC	

Project No.: 4143.3 Project: Route 65 / Pleasant Grove Creek Bridge ● Location: B97-9; BC-10-3 Date: 12-3-97	Remarks:
---	----------

GRAIN SIZE DISTRIBUTION TEST REPORT




Test	%+75mm	% GRAVEL	% SAND	% SILT	% CLAY
● 3	0.0	22.6	55.6	21.8	

LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
●		12.88	0.83	0.41	0.145				

MATERIAL DESCRIPTION	USCS	AASHTO
● Dark brown clayey sand with gravel	SC	

Project No.: 4143.3 Project: Route 65 / Pleasant Grove Creek Bridge ● Location: B97-10; B-1 Date: 12-3-97	Remarks:
--	----------

GRAIN SIZE DISTRIBUTION TEST REPORT



Test	%+75mm	% GRAVEL	% SAND	% SILT	% CLAY
● 9	0.0	9.8	56.1	34.1	


LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
●		3.24	0.60	0.36					

MATERIAL DESCRIPTION	USCS	AASHTO
● Dark yellowish brown silty sand	SM	

Project No.: 4143.3
 Project: Route 65 / Pleasant Grove Creek Bridge
 ● Location: B97-10; B-2
 Date: 1-2-98

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT



Test	%+75mm	% GRAVEL	% SAND	% SILT	% CLAY
● 5	0.0	33.3	45.5	21.2	


LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
●		13.34	2.99	1.24	0.209				

MATERIAL DESCRIPTION	USCS	AASHTO
● Dark yellowish brown silty sand with gravel	SM	

Project No.: 4143.3
 Project: Route 65 / Pleasant Grove Creek Bridge
 ● Location: B97-10; B-5
 Date: 12-26-97

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT



Test	%+75mm	% GRAVEL	% SAND	% SILT	% CLAY
● 10	0.0	7.6	66.2	26.2	


LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
●		1.46	0.40	0.23	0.094				

MATERIAL DESCRIPTION	USCS	AASHTO
● Dark yellowish brown silty sand	SM	

Project No.: 4143.3
 Project: Route 65 / Pleasant Grove Creek Bridge
 ● Location: B97-10; B-6
 Date: 1-2-98

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT




Test	%+75mm	% GRAVEL	% SAND	% SILT	% CLAY
● 6	0.0	20.3	61.0	18.7	

LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
●		6.76	1.43	0.90	0.237				

MATERIAL DESCRIPTION	USCS	AASHTO
● Dark yellowish brown silty sand with gravel	SM	

Project No.: 4143.3 Project: Route 65 / Pleasant Grove Creek Bridge ● Location: B97-10; B-7 Date: 12-26-97	Remarks:
---	----------



Sunland Analytical Lab, Inc.

11353 Pyrites Way, Suite 4
Rancho Cordova, CA 95670
(916) 852-8557

Date Reported 01/09/98
Date Submitted 01/06/98

To: Craig Newport
Anderson Consulting Group
631 Commerce Dr.
Roseville, CA 95678

From: Gene Oliphant, Ph.D. *GO*
General Manager

The following is the report of analysis requested on SUN Order 18592.
Your purchase order number is .
Thank you for your business.

SUN #	Sample Describ	Sample #	Chloride as ppm Cl /Dry Wt.	Sulfate as ppm SO4 /Dry Wt.
41178	4143.3/B97-8;L-2		29.6	36.3
41179	4143.3/B97-8;B-3		14.8	12.1

Methods: Sulfate-Cal Trans #417, Chloride-Cal Trans #422

